



**Information & Communication Technology Division, Head Office, Dhaka**

**Date: November 01, 2022**

<b>Tender Name: Lot-3 Tender Name: Amendment features of tender notice for Design, Supply, Erection, Testing &amp; Commissioning of one (01) Unit of 500 KVA Sub-Station including Cable &amp; Substation ECR (Electrical Control Room) civil work.</b>	
<b>RFP Ref: FSIBL/ICT/HO/624 /2022</b>	<b>Tender Floating Date: 05-October-2022</b>

Item No.	Tender Document Reference	Page	Tender Document Requirement	After Amendment
01	Roll out plan	08	Delivery of all the equipment must be completed within 60 days and installation work within 90 days from the date of issuance of work order.	Project completion (including delivery, installation, commissioning, testing etc.) should be done within 180 days from the date of issuance of work order.
02	Last Date of Submission:	05	06-Nov-2022; 2:30PM	Lot: 3: 15-Nov-2022, 2:30PM
03	GENERAL TERMS AND CONDITIONS	10	Warranty period of 3 (three) years will start after successful implementation and testing of the project. The AMC will start after the end of the warranty period which is from the 4th year (as applicable). Both the warranty and AMC should be backed by a similar back-to-back warranty/ AMC between the bidder and the manufacturer/OEM for FSIBL project	Warranty period of 2 (Two) years will start after successful implementation and testing of the project. The AMC will start after the end of the warranty period which is from the 4th year (as applicable). Both the warranty and AMC should be backed by a similar back-to-back warranty/ AMC between the bidder and the manufacturer/OEM for FSIBL project
04	LT Switchgear 800A	18	LT Switchgear 800A 5 set	LT Switchgear 800A as per SLD
05	HT & LT Busbar Trunking System	18	HT & LT Busbar Trunking System 1 Lot	HT & LT Panel internal connection must be busbar system.
06	Earthing System	19	Earthing System 1 set	Earthing System as per requirement



*Signature*

**Information & Communication Technology Division, Head Office, Dhaka**

**Date: November 01, 2022**

07	Isolation Transformer	19	Isolation Transformer 320 KVA	Isolation Transformer 400 KVA
08	Type Tested Cast Resin Dry Type Transformer	25	Type Tested Cast Resin Dry Type Transformer	Type Tested Cast Resin Dry Type 500 KVA Transformer with Enclosure.
09	300 KVAR Automatic PFI Plant	28	Type Test Certificates shall be submitted at the time of Technical Submission	Type Test or routine test Certificates shall be submitted at the time of Technical Submission.
10	11 KV Automatic Voltage Regulator (AVR)	22	Type Test Certificates shall be submitted at the time of Technical Submission	Type Test or routine test Certificates shall be submitted at the time of Technical Submission.
11	11 KV HT Incoming VCB	23	Country of origin (USA/ EU/ UK/ Switzerland/ Germany)	Please Specify
12	LT Switchgear	27	Type Test Certificates shall be submitted at the time of Technical Submission	Type Test or routine test Certificates shall be submitted at the time of Technical Submission.
13	ECR Room Cooling System	31	Exhaust Fan with air filter for (Natural Air in and Out) and CAC Air-condition supply by the Bidder.  Air-condition Brand Must be: General	CAC Air-condition supply by the Bidder. Air-condition Brand Must be: General
14	Payment terms	14	a. 50% of the total value on the signing of the PO against Bank Guarantee of the same amount with a validity of one year will be paid. BG will be released after supply and successful	i. 50% of the total value on the signing of the PO against Bank Guarantee of the same amount with a validity of 9 months will be paid. BG will be released after supply and successful installation. Otherwise, 50% may be paid after delivery. ii. 50% after successful delivery, installation, commissioning & UAT. A



**Information & Communication Technology Division, Head Office, Dhaka**

**Date: November 01, 2022**

			installation. Otherwise, 50% may be paid after successful installation. <b>b.30% after UAT</b> <b>c. Remaining 20% will be paid 2 months after the last payment</b>	Performance Security of 10% of the Total Amount should be furnished by the contractor as Bank Guarantee, otherwise this 10% of the Total Amount will be deducted from the final bill.
15	ACB and MCCB No of pole	As per discussion at Pre-bid meeting.		Except the isolation transformer incomer ACB, the rest of the ACB and MCCB will be 4 poles.
16	Cable Size	As per discussion at Pre-bid meeting		The cable size will be according to the rating of the breaker.
<b>Price offer</b>				
17	Price with HT AVR Set	As per discussion at Pre-bid meeting.		
18	Price without HT AVR Set	As per discussion at Pre-bid meeting.		



  
02/11/2022  
**Head of ICT Division**